

# Safe Work Method Statement

Switchboard upgrade & split system circuit

Sample Electrical Pty Ltd · ABN 12 345 678 901

|             |                                |
|-------------|--------------------------------|
| Site        | 14 Example Ave, Marion SA 5043 |
| Prepared    | 30 Sep 2026 · Rev 0            |
| Review by   | 6 Oct 2026 (end of job)        |
| Legislation | WHS Regulations 2012 (SA)      |

DRAFT

**Scope of work:** Replace the existing switchboard with a new enclosure fitted with RCBOs, and run a new dedicated circuit through the roof space to a split-system air conditioner. Mount the outdoor-unit wall bracket at about 2.4 m. Test, re-energise and issue a Certificate of Compliance.

**Review before use.** Drafted from a short description — the person responsible must check it before work starts. Confirm or fix:

1. Business address — not provided

2. Crew: Liam Kerr is second worker and was consulted

3. Licences held: SA electrical worker's licence (Dan), White Card (both), working at heights

4. House age / panel type — asbestos assumed possible

5. SA Power Networks service-fuse withdrawal booked

6. Whether solar PV or a battery is connected
7. Access equipment for the 2.4 m bracket (mobile scaffold vs ladder)

8. Dan Rossi is first aider and the kit is in the van

9. Assembly point: front footpath at the ute

10. Hospital drive time

11. Risk ratings — confirm they reflect your experience of this work

## 1 BUSINESS & JOB

|                  |                                                 |
|------------------|-------------------------------------------------|
| PCBU             | Sample Electrical Pty Ltd                       |
| ABN              | 12 345 678 901                                  |
| Address          | CHECK: not provided                             |
| Contact          | Dan Rossi · 0400 000 000                        |
| Work site        | 14 Example Ave, Marion SA 5043                  |
| Site status      | Occupied — 2 adults, 1 child, dog (kept inside) |
| Start / duration | 6 Oct 2026 · 1 day                              |

### REVISION HISTORY

| Rev | Date        | Change                    | By        |
|-----|-------------|---------------------------|-----------|
| 0   | 30 Sep 2026 | Draft prepared for review | Dan Rossi |
|     |             |                           |           |

## 2 PEOPLE & EQUIPMENT

|                       |                                                                                                                                          |
|-----------------------|------------------------------------------------------------------------------------------------------------------------------------------|
| Implements & monitors | Dan Rossi                                                                                                                                |
| Reviews this SWMS     | Dan Rossi                                                                                                                                |
| Workers consulted     | Dan Rossi, Liam Kerr CHECK: confirm                                                                                                      |
| Licences / tickets    | SA electrical worker's licence; White Card; working at heights<br>CHECK: confirm held                                                    |
| Plant & tools         | Platform ladder / mobile scaffold, drills, insulated hand tools, proved voltage tester, IR tester, crawl boards, LED light, lock-out kit |
| Hazardous substances  | Possible asbestos in existing meter panel; ceiling insulation dust                                                                       |
| PPE (minimum)         | Safety boots, eye protection, Class 00 insulating gloves, arc-rated shirt, P2 respirator                                                 |

### 3 HIGH RISK CONSTRUCTION WORK — IDENTIFICATION

Tick every category this work involves. **A SWMS is required if any box is ticked.** Each ticked item is cross-referenced to the job steps where it arises (section 4).

| No. | High risk construction work                                                                | Involved?                                                           | Job steps | How it arises on this job                                                                      |
|-----|--------------------------------------------------------------------------------------------|---------------------------------------------------------------------|-----------|------------------------------------------------------------------------------------------------|
| 1   | <b>Risk of a person falling more than 2 m</b>                                              | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | 6         | Mounting outdoor-unit bracket at ~2.4 m from ladder/platform <b>CHECK: confirm fall height</b> |
| 2   | Work on a telecommunication tower                                                          | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | —         |                                                                                                |
| 3   | Demolition of an element of a structure that is load-bearing                               | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | —         |                                                                                                |
| 4   | Demolition of an element related to the physical integrity of a structure                  | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | —         |                                                                                                |
| 5   | <b>Likely to involve disturbing asbestos</b>                                               | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | 2, 4      | Pre-1990 meter panel may contain asbestos; not to be drilled or broken                         |
| 6   | Temporary load-bearing support for structural alterations or repairs                       | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | —         |                                                                                                |
| 7   | Work in or near a confined space                                                           | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | —         |                                                                                                |
| 8   | Work in or near a shaft or trench deeper than 1.5 m, or a tunnel                           | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | —         |                                                                                                |
| 9   | Use of explosives                                                                          | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | —         |                                                                                                |
| 10  | Work on or near pressurised gas distribution mains or piping                               | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | —         |                                                                                                |
| 11  | Work on or near chemical, fuel or refrigerant lines                                        | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | —         |                                                                                                |
| 12  | <b>Work on or near energised electrical installations or services</b>                      | <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No | 3, 4, 7   | Switchboard replacement, cable run and testing near live parts                                 |
| 13  | Work in an area that may have a contaminated or flammable atmosphere                       | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | —         |                                                                                                |
| 14  | Tilt-up or precast concrete elements                                                       | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | —         |                                                                                                |
| 15  | Work on, in or adjacent to a road, railway, shipping lane or other traffic corridor in use | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | —         |                                                                                                |
| 16  | Work in an area with movement of powered mobile plant                                      | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | —         |                                                                                                |
| 17  | Work in areas with artificial extremes of temperature                                      | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | —         |                                                                                                |
| 18  | Work in or near water or other liquid with a risk of drowning                              | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | —         |                                                                                                |
| 19  | Diving work                                                                                | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | —         |                                                                                                |

Identified by: **Dan Rossi** Date: 30 Sep 2026 Signature: \_\_\_\_\_ If other high risk work comes up during the job, stop and review this SWMS.

#### 4 JOB STEPS, HAZARDS AND CONTROLS

| # | Job step                                 | High risk work              | Hazards and risks                                                                                                                                                                                                              | Risk     | Control measures                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Residual | Responsible |
|---|------------------------------------------|-----------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-------------|
| 1 | Arrive, brief occupants and assess       | —                           | <ul style="list-style-type: none"> <li>Occupants, children or pets entering work area → trips, contact with exposed parts</li> <li>Unexpected site conditions (damaged board, roof access) → work proceeds unsafely</li> </ul> | M<br>3×2 | <ul style="list-style-type: none"> <li><b>ISO</b> Barricade switchboard area and roof access with bollards/tape; agree no-go zone with occupants</li> <li><b>ADMIN</b> Walk the site before unloading; confirm scope and switchboard location with homeowner</li> <li><b>ADMIN</b> Tell occupants when power will be off and for how long</li> </ul>                                                                                                                 | L<br>1×2 | Dan Rossi   |
| 2 | Inspect switchboard backing for asbestos | 5 Asbestos                  | <ul style="list-style-type: none"> <li>Meter panel may contain asbestos (common in pre-1990 SA homes) → inhaling fibres if drilled or broken</li> </ul>                                                                        | H<br>3×4 | <ul style="list-style-type: none"> <li><b>ELIM</b> Do not drill, cut or break the existing panel; if replacement needed, SA Power Networks / licensed asbestos removalist removes it</li> <li><b>ADMIN</b> Treat any black/brown compressed-fibre board as asbestos unless tested <u>CHECK: confirm house age / panel type</u></li> <li><b>PPE</b> P2 disposable respirator available if panel must be handled</li> </ul>                                            | L<br>1×4 | Dan Rossi   |
| 3 | Isolate supply and prove de-energised    | 12 Electrical               | <ul style="list-style-type: none"> <li>Contact with live parts → electric shock, arc flash, death</li> <li>Supply re-energised by others while working</li> </ul>                                                              | E<br>4×5 | <ul style="list-style-type: none"> <li><b>ISO</b> Isolate at main switch; arrange SAPN service-fuse withdrawal for board replacement <u>CHECK: confirm SAPN booking</u></li> <li><b>ISO</b> Lock out and tag isolation point; keep the key on you</li> <li><b>ADMIN</b> Test-before-touch with a proved voltage tester (prove–test–prove) on every conductor</li> <li><b>PPE</b> Insulating gloves and arc-rated clothing for any testing near live parts</li> </ul> | M<br>1×5 | Dan Rossi   |
| 4 | Replace switchboard and fit new circuit  | 12 Electrical<br>5 Asbestos | <ul style="list-style-type: none"> <li>Residual live conductors (consumer mains, solar/battery backfeed) → shock</li> <li>Sharp edges, manual handling of new enclosure → cuts, strain</li> </ul>                              | H<br>3×5 | <ul style="list-style-type: none"> <li><b>ISO</b> Isolate and tag any solar inverter / battery (AC and DC) before opening board <u>CHECK: confirm if solar/battery present</u></li> <li><b>ENG</b> Insulated tools and shrouding on any conductor that cannot be de-energised</li> <li><b>PPE</b> Cut-resistant gloves when handling enclosures and cable tray</li> </ul>                                                                                            | M<br>1×5 | Dan Rossi   |

| # | Job step                                            | High risk work | Hazards and risks                                                                                                                                                                                                                                             | Risk     | Control measures                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Residual | Responsible           |
|---|-----------------------------------------------------|----------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------------|
| 5 | Work in roof space to run cable                     | —              | <ul style="list-style-type: none"> <li>Heat in roof space (often 45 °C+ in summer) → heat stress</li> <li>Falling through ceiling / off ladder → fractures</li> <li>Existing live cables, vermin, loose-fill insulation → shock, bites, irritation</li> </ul> | H<br>4×3 | <ul style="list-style-type: none"> <li><b>ADMIN</b> Schedule roof-space work before 11 am on hot days</li> <li><b>ENG</b> Walk only on joists; use crawl boards across ceilings; portable LED lighting</li> <li><b>ADMIN</b> Maximum 20 minutes in the roof space then a break with water; buddy stays at the manhole</li> <li><b>PPE</b> P2 respirator, long sleeves, gloves, eye protection</li> </ul>                                                              | M<br>2×3 | Dan Rossi             |
| 6 | Mount outdoor unit bracket at 2.4 m and run conduit | 1 Falls >2 m   | <ul style="list-style-type: none"> <li>Fall from ladder while drilling/fixing → head injury, fractures</li> <li>Dropped tools/bracket → struck-by injury to people below</li> </ul>                                                                           | H<br>3×4 | <ul style="list-style-type: none"> <li><b>SUB</b> Use a mobile scaffold or platform ladder rather than a single-stile ladder <u>CHECK: confirm access equipment</u></li> <li><b>ENG</b> Ladder footed on firm level ground, secured at top, 1:4 angle; three points of contact</li> <li><b>ISO</b> Exclusion zone below work area; no occupants within 2 m</li> <li><b>ADMIN</b> Tool lanyards; bracket lifted by second worker, not carried up the ladder</li> </ul> | M<br>2×3 | Dan Rossi / Liam Kerr |
| 7 | Terminate, test and re-energise                     | 12 Electrical  | <ul style="list-style-type: none"> <li>Incorrect connection → shock or fire on re-energising</li> <li>Re-energising while someone is still working</li> </ul>                                                                                                 | H<br>3×4 | <ul style="list-style-type: none"> <li><b>ADMIN</b> Complete insulation resistance, polarity and earth continuity tests before energising</li> <li><b>ADMIN</b> Verbal all-clear from every worker; remove own lock and tag last</li> <li><b>ADMIN</b> Issue Certificate of Compliance (CoC) to owner</li> </ul>                                                                                                                                                      | L<br>1×4 | Dan Rossi             |
| 8 | Clean up and hand over                              | —              | <ul style="list-style-type: none"> <li>Offcuts, dust, open manhole → trips and falls for occupants</li> </ul>                                                                                                                                                 | M<br>3×2 | <ul style="list-style-type: none"> <li><b>ADMIN</b> Remove all waste and offcuts from site</li> <li><b>ADMIN</b> Close manhole, remove barricades last, walk the site with homeowner and explain new board</li> </ul>                                                                                                                                                                                                                                                 | L<br>1×2 | Dan Rossi             |

Controls, most to least effective: **ELIM** Eliminate **SUB** Substitute **ISO** Isolate **ENG** Engineering **ADMIN** Administrative **PPE** Protective equipment

| Likelihood ↓ / Consequence → | 1 Insignificant                                                   | 2 Minor | 3 Moderate | 4 Major | 5 Catastrophic |
|------------------------------|-------------------------------------------------------------------|---------|------------|---------|----------------|
|                              | Score = L × C · Low 1–4 · Medium 5–9 · High 10–16 · Extreme 20–25 |         |            |         |                |
| 5 Almost certain             | 5                                                                 | 10      | 15         | 20      | 25             |
| 4 Likely                     | 4                                                                 | 8       | 12         | 16      | 20             |
| 3 Possible                   | 3                                                                 | 6       | 9          | 12      | 15             |
| 2 Unlikely                   | 2                                                                 | 4       | 6          | 8       | 10             |
| 1 Rare                       | 1                                                                 | 2       | 3          | 4       | 5              |

## 5 EMERGENCY

|                       |                                                                                                                                                  |
|-----------------------|--------------------------------------------------------------------------------------------------------------------------------------------------|
| Emergency services    | 000 (112 from a mobile with no coverage)                                                                                                         |
| Nearest hospital (ED) | Flinders Medical Centre, Flinders Dr, Bedford Park · approx. 8 min <u>CHECK: verify</u>                                                          |
| First aider / kit     | Dan Rossi · kit in the van <u>CHECK: confirm</u>                                                                                                 |
| Assembly point        | Front footpath at the ute <u>CHECK: confirm</u>                                                                                                  |
| Isolation points      | Main switch at meter box (front of house); SAPN service fuse                                                                                     |
| Stop work if          | Suspected asbestos is damaged · unexpected voltage detected · roof space unbearably hot or anyone unwell · wind or rain makes ladder work unsafe |

## 6 IMPLEMENTING, MONITORING & REVIEW

|                               |                                                                                                                                                                                                                                                                                                                                                                                                   |
|-------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| How controls are put in place | Dan Rossi briefs all workers on this SWMS before work starts; everyone signs on. Isolation and lock-out verified by Dan before any conductor is touched; ladder/platform set-up checked before first climb.                                                                                                                                                                                       |
| How controls are checked      | Dan Rossi checks controls at the start of the day and at each change of task (board → roof space → bracket → testing); confirms roof-space break times. Workers stop work and report if a control is missing or not working.                                                                                                                                                                      |
| Review date                   | 6 Oct 2026 (end of job) — or sooner if a trigger occurs                                                                                                                                                                                                                                                                                                                                           |
| Must be reviewed when         | <ul style="list-style-type: none"><li>• The work, system of work or location changes</li><li>• A new hazard or new information about a risk is identified</li><li>• A control is found not to be effective, or is changed</li><li>• A notifiable incident occurs during the work</li><li>• The SWMS is not being followed</li><li>• Before the work starts at each new site (if reused)</li></ul> |
| Legislation                   | Work Health and Safety Act 2012 (SA) · WHS Regulations 2012 (SA), Part 6.3 · Code of Practice: Construction Work · Regulator: SafeWork SA                                                                                                                                                                                                                                                         |

## 7 WORKER SIGN-ON

By signing I confirm this SWMS has been explained to me, I understand it, and I will follow it. I will stop work and tell my supervisor if I can't.

| Name | Company | Licence / ticket no. | Signature | Date |
|------|---------|----------------------|-----------|------|
|      |         |                      |           |      |
|      |         |                      |           |      |
|      |         |                      |           |      |
|      |         |                      |           |      |
|      |         |                      |           |      |
|      |         |                      |           |      |
|      |         |                      |           |      |